Notice dated 1st August 1916.

CONSTRUCTION OF RAILWAY CENTRAL OFFICES AT MYSORE.

Sealed tenders will be received at the Office of the Agent, Mysore State Railways, 15, Infantry road, Bangalore, up to 12 noon, on the 29th August 1916, for constructing Railway Central Offices at Mysore. A schedule showing approximate quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1917.

2. The plans and specifications may be seen at the Agent's Office at Bangalore, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Agent's Office and should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Railway Central Offices at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Agent, who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Agent's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money or rejected tenders will be returned.

Schedule showing the probable quantity of work to be done for constructing Railway Central Offices at Mysore.

Estimate of the probable quantities of constructing Railway Central Offices at Mysore.

No.	Items of work	Per	Ground floor	First floor
			Quantity.	Quantity.
1	Earth excavation	C. yds.	935	...
2	Chunam concrete foundation	C. ft.	8,800	...
3	Burnt stone in chunam foundation and basement	„	18,683	...
4	Burnt stone slabs 6" thick roughly dressed... ...	S. ft.	3,184	207
5	Platform made bricks in chunam superstructure	C. ft.	21,935	20,749
6	Do do arch work including centring ...	„	2,712	2,241
7	Plastering with mortar	Sqr.	293·36	348·38
8	White and colourwashing	„	293·36	348·38
9	Light cornice 9"×4½"	R. ft.	903	909
10	String courses	„	503	509
11	Crown of arches (ornamental)	each	50	59
12	Heavy cornice 12"×12"	R. ft.	457	807
13	Pucca terrace 9" thick (as per specification)	Sqr.	81·69	95·07
14	Rolled steel beam B.S. 21 (12"×6") at 44 lbs. per R. ft., including painting.	Cwt.	128	109·21
15	Teakwood work wrought and put up including wood oiling ...	C. ft.	813·40	877·72
16	Do doors 1½" thick shutters ½ pannelled and ½" glazed, etc., complete.	S. ft.	1,513	1,512
17	Teakwood windows 1½" thick shutters inside glazed, outside pannelled with iron bars, etc., complete.	„	345	315
18	Teakwood ventilators 1¼" thick shutters glazed with iron bars, etc., complete.	„	28	Nil
19	Teakwood fan lights ... do do do ...	„	401	421
20	Flooring with marsellies tiles over 3" concrete bed with cement pointing.	Sqr.	38·00	74·82
21	Chunam pointing	„	13·40	...
22	Silicate painting 3 coats to doors and windows and also to ventilators ...	„	41·88	43·90
23	Flooring with Cuddappa slabs 2" thick over 3" concrete bed and cement pointed.	„	33·36	...
24	Ornamental railings wrough iron 2½ feet high	R. ft.	...	225
25	Bricks in chunam parapet wall including plastering 2 feet high ...	„	...	776

K. KRISHNIENGAR,
Agent, Mysore State Railways.